

10-16-87

API NUMBER 15-093-20,906-0000

150' N

SE NW, SEC. 21, T 24 S, R 36 W/E

3450 feet from S section line

3300 feet from E section line

Lease Name Neff Well # 1

County Kearny 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1932

To: 1 050949
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5360

Operator: Brandt Production Company, Inc.
Name &
Address 105 South Broadway, Suite 920
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling Inc. License Number 5382

Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 1 p.m. Day: 16 Month: 10 Year: 19 87

Plugging proposal received from Jack Pepper

(company name) Cheyenne Drilling Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3070'
1st plug at 2800' with 125 sx cement, Anhydrite 1900'

2nd plug at 1960' with 50 sx cement,

3rd plug at 900' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 p.m. Day: 16 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2800' with 125 sx cement,

2nd plug at 1960' with 50 sx cement, 10-29-87

3rd plug at 900' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1987

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

Plugging not observed this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 10-30-87

INV. NO. 18721

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date: October 1, 1987 month day year

API Number 15-093-20,906-0000 150' N SE. NW. Sec. 21. Twp. 24. S. Rg. 36. West 3450 Ft. from South Line of Section 3300 Ft. from East Line of Section

OPERATOR: License # 5360 Brandt Production Company, Inc. 105 South Broadway, Suite 920 Wichita, Kansas 67202 Contact Person: Earl O. Brandt Phone 316/267-4335

Nearest lease or unit boundary line 660 feet County: Kearny

CONTRACTOR: License # 5840 Brandt Drilling Company, Inc. Wichita, Kansas 67202

Lease Name: NEFF Well # 1 Ground surface elevation 3070 feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO X Expl X Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: X yes no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 200-250 Depth to bottom of usable water 300 680

Surface pipe by Alternater IX 2 Surface pipe planned to be set 1900+

Conductor pipe required None Projected Total Depth 5100 feet

Formation St. Louis

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9-18-87 Signature of Operator or Agent Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 700 feet per Alt. 1

This Authorization Expires 3-23-88 Effective 9-28-87 Approved By P.H. 9-23-87

Jack Pepper 2000' sports-b 10' wch now water well Chapman's on hold

150' N SE. NW. Sec. 21. Twp. 24. S. Rg. 36. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2800' B. Council. G. feet depth with 125. SX. 60-40. Poz. 2nd plug @ 1900' B. Surf. Casg. feet depth with 35. SX. 60-40. Poz. 3rd plug @ 75' in. surf. Casg. feet depth with 25. SX. 60-40. Poz. 4th plug @ feet depth with 5th plug @ feet depth with (2) Rathole with 10. (b) Mousehole with None

PUSHER Jack Pepper TD 5100 FORMATION St LOUIS SURFACE PIPE 8 5/8 @ 1932 ANHYDRITE 1900 ELEVATION 3070 STARTING TIME & DATE 10-16-87 1:00 PM COMPLETION TIME & DATE 10-16-87 5:00 PM 1st PLUG @ 2800 FT. W/ 125 SX 2nd PLUG @ 1960 FT. W/ 50 SX 3rd PLUG @ 900 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Hall

TECHNICIAN 60/40 po 6909e1 RECEIVED STATE CORPORATION COMMISSION OCT 29 1987 CONSERVATION DIVISION Wichita, Kansas