

1 070286

JAN 3 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-093-20,866-0000

C NE NE, SEC. 19, T 24 S, R 36 W/E

4620 feet from S section line

660 feet from E section line

Lease Name Waechter Well # 1-19

County Kearny 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1864

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: Berexco Inc.
Name & Address 970 Fourth Financial Center
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco Inc. License Number 5147

Address 401 E. Douglas, #402, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 2 Month: 1 Year: 19 87

Plugging proposal received from Stan Wyckoff

(company name) Beredco Inc. (phone) 316-624-2434

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2900' with 100 sx cement, 2nd plug at 1860' with 50 sx cement,

3rd plug at 720' with 25 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 a.m. Day: 3 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2900' with 100 sx cement,

2nd plug at 1860' with 50 sx cement,

3rd plug at 720' with 25 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel. by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-20-87

INV. NO. 15-950

1-3

JAN 20 1987

CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Goodson
(TECHNICIAN)

1-20-87