

1 100080

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SE SE NW, SEC. 18, T24 S, R 36  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 093-20,858 - 0000  
2970 feet from ~~SPS~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

2970 feet from ~~SPS~~ section line

Lease Name Loucks Well # 1-18

Operator: Chevron U.S.A., Inc.  
Name & Address P. O. Box 12116  
Oklahoma City, OK 73157

County Kearny 168.87

Well Total Depth 5196 St. Louis feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 2001

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sage Drilling Co., Inc. License Number 5421

Address 202 South St. Francis, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 14 Month: March Year: 1986

Plugging proposal received from Mike Russell

(company name) Sage (phone) 316-263-6139

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3000' with 80 sx cement

2nd plug at 2010' with 40 sx cement

3rd plug at 875' with 25 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 pm Day: 14 Month: March Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement, 2nd plug at 2010' with 45 sx cement, 3rd plug at 875' with 25 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 20 sx cement, 7th plug to circulate mouse hole with 20 sx cement.

STATE CORPORATION COMMISSION

3-20-86 MAR 20 1986

Remarks: Used Class H Cement by Dowell 03-12-8619 (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED observe this plugging.

Signed Phyllis Wiley (TECHNICIAN)

DATE MAR 20 1986

INV. NO. 13018

3-14

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 3 3 86  
month day year

API Number 15- 093-20,858-0000

OPERATOR: License # 4519  
Name: Chevron U.S.A. Inc.  
Address: P.O. Box 12116  
City/State/Zip: Oklahoma City, OK 73157  
Contact Person: Curtis Williams  
Phone: (405) 949-7000

SE SE NW/4 18 24 36  East  
(location) Sec Twp S, Rge  West  
2970  
2970 Ft North from Southeast Corner of Section  
Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107  
Name: H-30 Drilling, Inc. Sage Rig 2  
City/State: Wichita, KS

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

If OWWO: old well info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp Date: \_\_\_\_\_ Old Total Depth: \_\_\_\_\_  
Projected Total Depth: 5200 feet  
Projected Formation at TD: St. Louis-Mississippian  
Expected Producing Formations: St. Louis, Marrow, Lansing

Nearest lease or unit boundary line: 330 feet  
County: Kearny  
Lease Name: Loucks Well# 1-18  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no  
Depth to Bottom of fresh water: 850 275 feet  
Lowest usable water formation: Cheyenne  
Depth to Bottom of usable water: 850 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set: 2,000 (ANHYDRITE) feet  
Conductor pipe if any required: 16" at 100 feet  
Ground surface elevation: 3219 feet MSL  
This Authorization Expires: 8-19-86  
Approved By: 2-19-86

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date: 2-19-86 Signature of Operator or Agent: Cindy Earnest Title: Operations Assistant  
Form C-1 4/84

set 2000' of 8 5/8 on 3/4/86 50' of 16"  
Mike Russell -

PUSHER	TD	SURFACE PIPE	ANHYDRITE	STARTING TIME & DATE	COMPLETION TIME & DATE	1st PLUG @	2nd PLUG @	3rd PLUG @	4th PLUG @	RAT HOLE CIRCULATED	MOUSE HOLE CIRCULATED	WATER WELL PLUGGED	CEMENT COMPAN	TECHNICIAN
Mike Russell	5196	8 5/8 @ 2001				Bottom plug 170' cement - 8	50' plug @ 170	2010	270	10 SX	W/10	W/10		
						FT. WI	FT. WI	FT. WI	FT. WI					

will call back

Chyde well make good  
Wise

STATE CORPORATION COMMISSION

MAR 20 1986

Wichita, Kansas