

1 051856

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-093-21,403-0000

App. NE NW SW, SEC. 18, T 7 24 S, R 36 W/X
2310 feet from S section line
1250 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135
Operator: John O. Farmer, Inc.
Name & Address: P.O. Box 352
Russell, KS 67665

Lease Name Loeppke "B" Well # 1
County Kearny 165.10
Well Total Depth 5080 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1602

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 1 a.m. Day: 23 Month: 10 Year: 1994

Plugging proposal received from Gary Fisher

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2003-2017'

- 1st plug at Hugoton/Council Grove with 100 sx cement,
- 2nd plug at 2017' with 40 sx cement, 3rd plug at 1640' with 50 sx cement,
- 4th plug at 800' with 40 sx cement, 5th plug at 40' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 23 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

- 2nd plug at 2017' with 40 sx cement,
- 3rd plug at 1640' with 50 sx cement,
- 4th plug at 800' with 40 sx cement,
- 5th plug at 40' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

DATE 11-2-94

INV. NO. 41561

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED
STAFF CORPORATION COMMISSION
OCT 28 1994
Wichita, Kansas