

To: 1 020798
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-13

API NUMBER 15-093-20,846-0000
C NW, SEC. 14, T 24 S, R 36 1/4
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5952
Operator: Amoco Production Company
Name: P.O. Box 800, Rm.925
Address: Denver, CO 80201

Lease Name Thomas GU A CG Well / 2
County Kearny 95.87
Well Total Depth 2950 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 814

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Amoco Production Company License Number 5952
Address P.O. Box 800, Rm. 925, Denver, CO 80201

Company to plug at: Hour: 10 a.m. Day: 13 Month: 9 Year: 19 94
Plugging proposal received from Joe Eudey
(company name) Amoco (phone) 316-356-6981

Perfs: 5 1/2" at 2912', TOC 1850', PBTD 2912', Perfs at 2709-90'
At an earlier date, perforated 5 1/2" at 1536-38', pumped 400 sx cement circulated to surface
1st plug fill 5 1/2" casing with 2 sx hulls and cement to surface.
Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 12:45 p.m. Day: 13 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 230 sx cement down 5 1/2" casing with 200 lbs. hulls
mixed in at the start of cement. Got pressure and shut in.
Checked annulus. Pumped 1/2 bbl. and pressured up to 700 psi.

9-16-94

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1994

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-28-94

INV. NO. 41287

observe this plugging.

Signed Glen R. Barlow
(TECHNICIAN)