

To: 1 080163  
STATE CORPORATION COMMISSION  
Wichita State-Office Bldg. - PLUGGING SECTION NE NE SW NE, SEC. 9, T 24 S, R 35 W/X  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 093-21,128 -0000

J  
R

11-25

3880 feet from S section line  
1360 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5952

Lease Name Bentrup Gas Unit Well / 2 HI

Operator: Amoco Production Company

County Kearny 87.43

Name: P.O. Box 800, Room 924  
Address: Denver, CO 80201

Well Total Depth 2690 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 824

Abandoned Oil Well Gas Well  Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address

Company to plug at: Hour: 1 p.m. Day: 25 Month: 11 Year: 19 97

Plugging proposal received from Joe Eudey

(company name) Amoco Production Company (phone) 316-356-6981

Work: 5 1/2" at 2690' w/700 sx cement, Slotted casing 2428-2690'

1st plug pump down 5 1/2" with 5 sx hulls and 250 sx cement,

Check backside.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 4:30 p.m. Day: 25 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 800 lbs. hulls ahead of cement with 200 lbs. hulls mixed in first 20 bbls. Let set 30 minutes. Pumped a total of 300 sx.cement.

2nd plug pumped 8 sx cement down 8 5/8" X 5 1/2", pressured to 500 psi.

12-4-97

Remarks: Used 65/35 Class C Pozmix by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

DATE 12-8-97

INV. NO. 49593

Signed Kevin D Strube (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC-11-1997