

1-26

To: 1 051127
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 093-20.961-0000
SW NE NW, SEC. 30, T 24 S, R 35 W4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4253

4030 feet from S section line

3930 feet from E section line

Operator: Plains Petroleum Operating Co.
Name & Address P.O. Box 15278
Lakewood, CO 80215

Lease Name Singleton Well # 1-I

County Kearny 86.13

Well Total Depth 2650 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling License Number 5382

Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 3:30 p.m. Day: 26 Month: 1 Year: 19 89

Plugging proposal received from Dave Leopold

(company name) Plains Petroleum Operating Company (phone) 316-355-7838

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2978'
Anhydrite 1860-70'

1st plug at 2650' with 50 sx cement, 2nd plug at 932' with 50 sx cement,

3rd plug at 412' with 50 sx cement, 4th plug at 30' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Rec'd 1-31-89

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11 p.m. Day: 26 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT Lost circulation at 2650', pipe stuck in hole at 2640',

ran free point, stuck at 1300-1050', backed off pipe at 1015', pulled 330' of pipe to
free it up, then redrilled to 932' to plug.

1st plug at 2650' with 50 sx cement, 2nd plug at 932' with 50 sx cement,

3rd plug at 412' with 50 sx cement, 4th plug at 30' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 2-3-89

INV. NO. 23865

1-26

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL
HUGOTON INFILL

Starting Date January 30, 1989
month day year

API Number 15-093-20,961-0000

OPERATOR: License # 4253
Name Plains Petroleum Operating Company
Address P.O. Box 15278
City/State/Zip Lakewood, CO 80215
Contact Person Jeff Carlson
Phone (303) 969-9325

Approx.-

SW. NE. NW. Sec. 30 Twp. 24 S, Rg. 35 W
4030 Ft. from South Line of Section
3930 Ft. from East Line of Section

CONTRACTOR: License # 5382
Name Cheyenne Drilling
City/State Garden City, KS

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells
Total number of acres attributed to unit 636
Nearest producing well from

Well Drilled as: New Recompletion OWWO
Projected Total Depth 2775 feet
Formation Chase

same common source of supply 2810 feet
Nearest lease or unit boundary line 1250 feet
County Kearny

If OWWO or Recompletion: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

Lease Name Singleton Well # 1-1
Ground surface elevation 2978 feet MSL
Depth to bottom of fresh water 320' 350'
Depth to bottom of usable water 780' 800'
Surface pipe by Alternate: 1 2
Surface pipe planned to be set 370'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 1-9-89 Signature of Operator or Agent J. Carlson Title Manager of Drlg. & Prod.

For KCC Use:

Conductor Pipe Required _____ feet; Minimum Surface Pipe Required 370' feet per Alt. (2)

This Authorization Expires 7-12-89 Approved By KM 1-12-89

EFFECTIVE DATE: 1-17-89

10/86

Move in 1-23-89 set 370' of 8 5/8"

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1989

CONSERVATION DIVISION
Wichita, Kansas

PUSHER Dave Leopold
TD 2650' FORMATION Towanda
SURFACE PIPE 8 5/8" @ 371'
1860' ELEVATION 2978
ANHYDRITE 1870'
STARTING TIME & DATE 7:30 p 1-26-89
COMPLETION TIME & DATE 11:00 p 1-26-89
1st PLUG @ 2650 FT. WI 50 SX
2nd PLUG @ 932 FT. WI 50 SX
3rd PLUG @ 412 FT. WI 50 SX
4th PLUG @ 30 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI _____ SX
WATER WELL PLUGGED WI _____ SX

CEMENT COMPANY Halliburton
TECHNICIAN Lacey Sawal
60/40 poz 690
circulation @ 2650
Last circulation in hole @ 2640
pipe stuck in hole @ 2640
ran free point
partially stuck at 1050'
stuck at 1300 to 1050'
Backed off pipe @ 1015
Spooled 330' of pipe to free it up
Then redrilled to 932 to plug