

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21221-00-00
Spot: CSENE Sec/Twnshp/Rge: 27-24S-35W
1980 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: NUSS B Well Number: 3
County: KEARNY Total Vertical Depth: 5050 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

Conductor Pipe: Size feet: #164.13
Surface Casing: Size 8.625 feet: 653
Production: Size 5.5 feet: 3128 WITH 745 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/09/2002 9:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: SPANKY SPOHN Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: FILL CASING WITH CEMENT TO SURFACE. PRESSURE CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/09/2002 12:35 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 3085'. OPEN HOLE PLUG 3128-3300'. PBTD 3085'. PERFS AT 2718-3020'. PUMPED DOWN 5 1/2" CASING WITH 700# HULLS & 326 SX CMT. FIRST 200 SX CMT WAS 60/40 POZMIX 2% CC & THE REMAINING SX OF CMT WERE 60/40 POZMIX 6% GEL. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 11 SX CMT. PRESSURED UP TO 500#.

RECEIVED
APR 21 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

INVOICED

DATE 4-23-02

APR 17 2002

INV. NO. 2002061688

Form CP-27