

2-1

To: 1 020209  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C N/2 of SW/4, SEC. 12, T 24 S, R 36 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 093-20,855-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952  
Operator: Amoco Production Company  
Name: Amoco Production Company  
Address: P.O. Box 800  
Denver, CO 80201

1980 feet from S section line  
3960 feet from E section line  
Lease Name White G.U. E Well # 2 CG E'  
County Kearny 96.85  
Well Total Depth 2980 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 830

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pullers License Number 6497  
Address Box F, Sublette, KS 67877

Company to plug at: Hour: 12:10 p.m. Day: 1 Month: 2 Year: 19 89

Plugging proposal received from Ed Eves  
(company name) Midwest Casing Pullers (phone) 316-675-8349  
were: 5 1/2" at 2904' Perfs at 2735-2816'-slots

1st plug set CIBP at 2600' and dump 2 sx cement on top,  
2nd plug pump 20 sx cement at 1600', 3rd plug pump 20 sx cement at 860',  
4th plug pump 5 sx cement at 40-0',  
5th plug pump 15 sx cement on annulus.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 1 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2600' with 2 sx cement on top,  
Gel mud between all plugs,  
2nd plug at 1600' with 20 sx cement, gel to 860',  
3rd plug at 860' with 20 sx cement,  
4th plug at 40-0' with 5 sx cement,  
5th plug 15 sx cement down annulus.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 7 1989  
2-7-89

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pullers. No casing recovered.  
(If additional description is necessary, use BACK of this form.)

(If ~~not~~ observe this plugging.

Signed Glenn R. Barber  
(TECHNICIAN)

INVOICED  
DATE 2-8-89  
INV. NO. 23911  
2-1