

To: 1110117  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,613-0000  
SE SE NW, SEC. 21, T 24 S, R 34 W/E  
2975 feet from S section line  
2975 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Orange Brown Well # 1

Operator: McCoy Petroleum Corporation  
Name & Address 110 South Main, Suite 500  
Wichita, KS 67202

County Finney 165.82  
Well Total Depth 5102 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1919

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address Drawer 1431, Duncan, OK 73536

Company to plug at: Hour: 7 p.m. Day: 13 Month: 10 Year: 19 88

Plugging proposal received from Darrel Hansen

(company name) McCoy Petroleum Corporation (phone) 316-254-7204

were: 5 1/2" at 5102' PBTD 5052' Perfs at 4782-4958' (4 sets) DV tool at 3203' w/200 sx cement

1st plug set CIBP above perfs at 4760' with 3 sx cement with dump bailer on plug,

load hole with gel mud,

2nd plug spot through tubing at 2014' with 50 sx cement,

3rd plug at 850' with 30 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 14 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4760' with 3 sx cement through dump bailer

on top of plug,

Circulated hole through tubing with gel.

2nd plug spotted through tubing with 50 sx cement at 2014'

3rd plug at 850' with 30 sx cement,

4th plug at 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2014' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (copy of xxxxxxxx) observe this plugging.

DATE 10-27-88

INV. NO. 22785

Signed James Rapp  
(TECHNICIAN)