

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22780-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 23-14S-20W
2314 feet from S Section Line, 2305 feet from E Section Line
Lease Name: HASELHORST Well #: 1-A
County: ELLIS Total Vertical Depth: 3764 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3763		150 sx
SURF	8.625	250		350 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2016 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-6964

Proposed Plugging Method: Ordered 340 sx 60/40 pozmix 4% gel cement, 14 sx gel and 600 # hulls.
Dig Safe # 16392647

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2016 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Xcel perforated at 2160', 1420', 676' and 300'. Quality ran in hole with tubing to 3700', rigged to tubing, mixed and pumped 14 sx gel followed by 50 sx cement w/150 # hulls mixed in. Pulled tubing to 1850' and pumped 145 sx cement w/250 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 45 sx cement to pressure with 450 psi. Shut in pressure 450 psi. Hooked to 8 5/8" surface casing and pumped 50 sx cement. No shut in pressure.

GPS: 38.81894 -099.51170

Perfs:


Remarks: QUALITY WELL SERVICE TICKET # 6126 KCC FEE FUND PROJECT CONTROL # ~~20130088-001~~

20130089-001

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

KCC WICHITA

AUG 18 2016

RECEIVED

AUG 15 2016