

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22469-00-01
Spot: NENWNE Sec/Twnshp/Rge: 16-24S-5E
5183 feet from S Section Line, 1663 feet from E Section Line
Lease Name: WALTERS B Well #: 12
County: BUTLER Total Vertical Depth: 2650 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2648		100 SX
SURF	8.625	209		250 SX

Well Type: EOR UIC Docket No: E26234.1 Date/Time to Plug: 07/19/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL COMPANY Phone: (620) 222-4304

Proposed
Plugging
Method:

As per KCC instructions

Plugging Proposal Received By: JONATHAN HILL WitnessType: NONE
Date/Time Plugging Completed: 07/20/2016 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

***Per operator's CP-4:
Ran tubing to 2600' and pumped 25 sacks of cement with 150 pounds of hulls and 3% CaCl.
Pulled tubing and perforated casing at 260'. Ran tubing to 260' and pumped 50 sacks of cement
which circulated out 4.5" casing. Pulled tubing out and pumped 80 sacks of cement down 4.5"
casing and filled to surface.

Perfs:

Top	Bot	Thru	Comments
2528	2540		

Remarks: KCC NOT CONTACTED PRIOR TO PLUGGING OPERATIONS. CEMENTING COMPLETED BY QUALITY
WELL SERVICE, ELLINWOOD, KS. TICKET #:6539

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

Form CP-2/3

AUG 18 2016
NO
CCUIC