

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-055,-20594-6000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Ensign Operating Co. OPERATORS LICENSE NO. 4782

ADDRESS P.O. Box 937, Garden City, Kansas 67846 PHONE # (316) 276-3267

LEASE (FARM) Carp WELL NO. RECEIVED WELL LOCATION NW/NW COUNTY Finney

SEC. 10 TWP. 24 RGE. 32 STATE CORPORATION COMMISSION (E) or (W) TOTAL DEPTH 4950 PLUG BACK TD 2988

Check One:

OIL WELL \_\_\_\_\_ GAS WELL x D & A Wichita, Kansas CONSERVATION DIVISION SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 1862 CEMENTED WITH 900 SACKS

CASING SIZE 5-1/2" SET AT 3050 CEMENTED WITH 280 SACKS

PERFORATED AT 2831-43, 2864-66, 2922-24

CONDITION OF WELL: GOOD x POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 25 Sk cement plug from 2750 to 2988'

Pull 5-1/2" casing from 1890' approx. Plug with cement at base of surface casing, at 900',

and at top of surface casing. Cut off and cap surface casing 3' below ground level.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Reed Wacker PHONE # (316) 276-3267

ADDRESS P.O. Box 937, Garden City, Kansas 67846

PLUGGING CONTRACTOR Midwest Casing Pullers LICENSE NO. 6479 6497

ADDRESS Sublette, Kansas PHONE # (316) 675-8349

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Reed Wacker  
(Operator or Agent)

DATE: 9/8/89

①

State of Kansas



## Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

September 13, 1989

**NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION**

Ensign Operating Co.  
P.O. Box 937  
Garden City, KS 67846

Carp 10-1  
NW/NW  
10-24-32W  
Finney County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #1 304 W. McArtor

Dodge City, KS 67846

(913) 225-6760