

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-055-20,820-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202 PHONE # (316) 265-9697

LEASE (FARM) Brown "B" WELL NO. 1-28 WELL LOCATION SE SE SE COUNTY Finney

SEC. 28 TWP. 24S RGE. 34W or TOTAL DEPTH 5075' PLUG BACK TD 5031'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1898' CEMENTED WITH 700 SACKS

CASING SIZE 5-1/2" SET AT 5071' CEMENTED WITH 175 SACKS
DV Tool @ 3158' W/110 Sacks

PERFORATED AT 4774-4776'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 4650' +/- Place 3 sx cement on top of COBP w/
dump bailer. Cut off and pull casing from approximately 2000'. Run tubing and circulate hole

with gel. Set plugs using 60-40 Pozmix, 6% gel as follows: Bottom of 50 sack plug @ 1990',
(If additional space is needed use back of form.) (OVER)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Will Notify Later

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Daryl Hanson
PHONE # (316) 532-5452

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Eldredge Well Service LICENSE NO. 9567

ADDRESS Satanta, KS 67870 PHONE # (316) 649-2841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: _____

(Operator or Agent)

DATE: _____

10-13-89

①

4/90

4/90

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1989
CONSERVATION DIVISION
Wichita, Kansas

Bottom of 30 sack plug @ 850' and Bottom 10 sack plug @ 40' to 3' below GL.



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE

JAN 17 1990

EXPIRES

October 17, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

McCoy Petroleum Corporation
 110 S. Main, Suite 500
 Wichita, KS 67202

Brown "B" 1-28
 Sec. 28-24-34W
 SE SE SE
 Finney County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
 Shari Feist Albrecht
 Director

District: #1 304 W. McArtor

 Dodge City, KS. 67801

 (316) 225-6760
