

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,594-0000

LEASE NAME Carp

WELL NUMBER 10-1

SPOT LOCATION NW-NW

SEC. 10 TWP. 24 RGE. 32 ~~W~~ (W)

COUNTY Finney

Date Well Completed 8/1/85

Plugging Commenced 9-20-89

Plugging Completed 9-22-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ensign Operating Co.

ADDRESS Box 937, Garden City, Ks. 67846

PHONE (316) 276-3267 OPERATORS LICENSE NO. 4782

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Hugoton Depth to top 2831' bottom 2924' T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	1862'	0'
Production				5 1/2"	3050'	1840'

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 25 sks. cement to 2600'
Pressured to 750 lbs. Pump 40 sks. cement 1820' to 1700' - Mud to 900'
Pump 40 sks. cement 900' to 780' - Mud 780' to 40'
Put bridge and 10 sks. cement 40' to 3'
Cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

T. Edgar J. Eves (employee of operator) or
(~~OWNER~~) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.



(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 26th day of Sept., 1989

Sondra L. Eves
Notary Public

My Commission expires: 12-6-92