

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-055-21,253-00-00

LEASE NAME Mayo "A" #1-15

WELL NUMBER \_\_\_\_\_

4290 Ft. from § Section Line

330 Ft. from § Section Line.

SEC. 15 TWP. 24S RGE. 32W(E) or (W)

COUNTY Finney

Date Well Completed 12/12/93

Plugging Commenced 12/12/93  
11:10 a.m.

Plugging Completed 12/12/93  
2:00 p.m.

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Landmark Oil Exploration, Inc.

ADDRESS 250 N. Water, Suite 308, Wichita, KS 67202

PHONE# (316) 265-8181 OPERATORS LICENSE NO. 06113

Character of Well P&A-Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/12/93 (date)

by Case Morris - Dodge City (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom T.D. 4929'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		surface		8-5/8"	1943'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 100 sacks @ 3040'; 50 sacks @ 2000'; 50 sacks @ 1150'; 40 sacks @ 600'; 10 sacks @ 40'; and 15 sacks in the rathole. Total of 265 sacks of 60/40 pozmix, 6% gel, 1/4# Floseal/sk  
JC: 2:00 p.m. 12/12/93 - Allied Cementing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30606

Address 250 N. Water, Suite 300, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Landmark Oil Exploration, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jeffrey R. Wood (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 250 N. Water, Suite 308, Wichita KS 67202

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 94



Karri Wolken  
Karri Wolken Notary Public

Commission Expires: February 7, 1996