


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 25 Twp. 30S Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Beacon Resources Corporation  
Lease Name Lechner Well No. 1  
Office Address 1000 Century Plaza Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 31, 1969  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced December 31, 1969  
Plugging completed December 31, 1969  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey of Augusta  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4695 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	289'	8-5/8"	289'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 235 Feet,  
1/2 sax Hulls, Plug and 35 sax Cement; Mud  
to 40 Feet, 1/2 sax Hulls, Plug Bridged  
with Kelly; 10 sax Cement to Base of Cellar;  
2 sax Cement in Rat Hole.  
Job Completed @ 5:45 A.M. on 12/31/69.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1969 1-5-69  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer  
500 Bitting Building, Wichita, Kansas 67202  
(Address)

Subscribed and SWORN to before me this 2nd day of January, 1970



Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

DRILLERS LOG

LECHNER NO. 1

CASING RECORD:	OPERATOR:	Beacon Resources Corporation	DESCRIPTION:
8-5/8" @ 289'	CONTRACTOR:	Sage Drilling Co., Inc.	C NW SE
w/225 sax cement	COMMENCED:	December 16, 1969	Sec. 25-30S-7W
TOTAL DEPTH:	COMPLETED:	December 31, 1969	Kingman Co., Kansas
4695'			ELEVATION: 1559 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Lime	0	289	
Shale & Shells	289	330	
Shale	330	1135	
Lime	1135	1300	
Lime & Shale	1300	1810	
Lime	1810	1985	
Shale & Shells	1985	2475	
Lime & Shale	2475	2913	
Shale & Lime	2913	3120	
Lime & Shale	3120	3355	
Lime	3355	3492	
Lime & Shale	3492	3738	
Shale & Lime	3738	3818	
Lime	3818	4060	
Shale	4060	4110	
Lime	4110	4172	
Lime, Shale & Marmaton	4172	4260	
Lime	4260	4312	
Mississippian Lime	4312	4408	
Lime	4408	4667	
Lime & Shale	4667	4695	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer  
Wayne W. Kahmeyer



Subscribed and sworn to before me this 2nd day of January, 1970.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.