

15-095-20651-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 31 Twp. 30S Rge. 7 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 150' NW of C NW SE

Lease Owner Associates Oil & Gas, Inc.
Lease Name Flowers Well No. 1

Office Address Suite 501, 120 Bldg., Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed November 7, 19 77
Application for plugging filed November 7, 19 77
Application for plugging approved November 7, 19 77
Plugging commenced November 7, 19 77
Plugging completed November 7, 19 77
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4810'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	227'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240 feet. Pumped 35 sacks of cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 77

Betty Brandt
Betty Brandt Notary Public.

My commission expires May 9, 1979

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1977
11-17-77
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLERS' LOG

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMMENCED: 29 October 1977
 910 Union Center
 Wichita, Kansas 67202

OPERATOR: Associates Oil and Gas, Inc. DRILLING COMPLETED: 6 November 1977
 Suite 501, 120 Bldg.
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 227' of used 8-5/8" LOCATION: Flowers No. 1
 cemented with 240 sacks 150' NW of C NW SE
 Section 31-30S-7W
 Kingman County, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 17 1977
 CONSERVATION DIVISION
 Wichita, Kansas

- 0 - 127 Sand & clay
- 127 - 227 Red bed
- 227 - 788 Sand & red bed
- 788 - 3015 Shale & lime
- 3015 - 3464 Lime & shale
- 3464 - 3620 Shale & lime
- 3620 - 4077 Lime & shale
- 4077 - 4810 Lime
- 4810 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves* President

STATE OF KANSAS)
)
 SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public, this 16th day of November, 1977.

My commission expires: 2 February 1980

Courtney M. Graves
 Courtney M. Graves Notary Public

