

15-095-01185-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

Byg


COMPANY Magnolia Petroleum Co.

SEC. 1 T. 30S R. 8W
LOC. SW NE NW

FARM Gwynn-Render NO. 1

TOTAL DEPTH 4240
COMM. 12/15/56 COMP. 1/18/57
SHOT OR TREATED
CONTRACTOR Graham-Michaelis Drlg.
ISSUED

COUNTY Kingman
KANSAS



CASING

20 XX 9 5/8" @ 240' & cem. w/250 sacks.
15 B
12 6
13 5 1/2" @ 4239' & cem. w/200 sacks.

ELEVATION 1545 D.F.

PRODUCTION

COF 7,856,000 CFGPD

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	385
Red Bed & Shale	1236
Anhydrite	1475
Anhydrite, Shale	1803
Shale & Lime	2503
Shale	2681
Lime & Shale	3438
Lime	3592
Shale & Lime	3667
Lime	3878
Lime & Shale	4240

TOPS:

Heebner Shale	3182
Douglas Group	3212
Douglas Sand	3316
Lansing-Kansas City	3412
Mississippi "Chat"	4140
Rotary Total Depth	4240

DST #1, 4143-70, Open 1 hr., gas to surface in 2 min., gauged 1,020 MCFG in 5 min., 1,250 MCFG in 10 min., 1,450,000 MCFG/20 min., and stab. at 1,450 MCFG for the remainder of test, rec. 65' GCM, IF 400#, FF 390#, IBHP 1625#, SI 20 min., FBHP 1570#, SI 20 min.

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1973
12-6-73
CONSERVATION DIVISION
Wichita, Kansas