

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-055-20,613-0000 (of this well) 6/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR McCoy Petroleum Corporation OPERATORS LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202 PHONE # (316) 265-9697

LEASE (FARM) Orange Brown WELL NO. 1 WELL LOCATION SE SE NW COUNTY Finney

SEC. 21 TWP. 24S RGE. 34 (S) or (W) TOTAL DEPTH 5102 PLUG BACK TD 5057'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ SOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1999 CEMENTED WITH 700 SACKS

CASING SIZE 5-1/2" SET AT 5102 CEMENTED WITH 320 SACKS

DV Tool @ 3203' Cemented with 200 sacks.

PERFORATED AT 4782-4808' 4849-4808' 4849-4854' 4952-4958'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 4750'. Place 2 sx cement on

top of CIBP with dump bailer. Place 50 sack plug (60-40 Posmix) @ 2000'. Place 30 sacks

plug (60-40 Posmix) @ 850'. Place 10 sack plug (60-40 Posmix) @ 40' to 3' below GL.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3-12-88 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 532-5452

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429 6/89

ADDRESS Attica, Kansas PHONE # (316) 254-7204

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: *Daryl Hanson*

(Operator or Agent)

DATE: 10-10-88



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. MENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.
GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
JAN 11 '89
EXPIRES

October 11, 1988

WELL PLUGGING NOTICE

Orange Brown #1
SE SE NW
Sec. 21-24S-34W
Finney County

McCoy Petroleum Corporation
110 S. Main, Ste. 500
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #1 304 W. McArtor, Dodge City, KS 67801 (316) 225-6760