

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 10 1966

CONSERVATION DIVISION
 WICHITA, KANSAS

1-10-1966

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Crendle of Sooner Pipe & Supply Corp. has this
 date requested permission to plug the following described well:

Mr. Crendle guarantees payment of the plugging fee.

Operator's full Name: Sooner Pipe & Supply Corp.

Complete Address: Box 1530 Tulsa, Okla.

Lease Name: H.A. Smalley Well No. # A-1

Location: NW NW SE Sec. 35 Twp. 24 Rge. 38 (E)(W)

County Kearney Total Depth 2686' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Crendle was instructed to plug the well as follows:

8 5/8"-670' Circulated w/cement. 5 1/2"-2662' Cemented.

Plug bottom w/20 Sax.cement top cement at 2500' Mud 2500' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 Sax.cement 45' to 0

Very truly yours,

[Signature]
 Conservation Division Agent