

State of Kansas



15-093-00370-0006

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1966
CONSERVATION DIVISION
Wichita, Kansas

1-12-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Crendle of Sooner Pipe & Supply Corp. has this

date requested permission to plug the following described well:

Mr. Crendle guarantees payment of the plugging fee.

Operator's full Name: Sooner Pipe & Supply Corp.

Complete Address: Box 1530 Tulsa, Okla.

Lease Name: Iman Wiatt Well No. # 1

Location: SE SE NW Sec. 22 Twp. 24 Rge. 38 (E) (W)

County Keahey Total Depth 2715' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Crendle was instructed to plug the well as follows:

8 5/8"-745'-Circulated W/Cement. 5 1/2"-2676' -Cemented.

Plug bottom w/20 Sax.cement top cement at 2550'.Mud 2550' to 800'

Spotted 35 Sax.cement 800' to 700'. Mud 700' to 45'

Plug,Hulls,15 Sax.cement 45' to 0.

Very truly yours,

Conservation Division Agent