



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
2-12-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Lahar of B & B Drilling, Inc. has this date requested permission to plug the following described well:

Mr. James A. Allison guarantees payment of the plugging fee.

Operator's full Name: Allison & Black

Complete Address: 1415 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Redetzke "A" Well No. # 1

Location: 75' E NE NW SW Sec. 10 Twp. 16 Rge. 11 (E)(W) W

County: Barton Total Depth 3369 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bill Lahar was instructed to plug the well as follows:

8 5/8" 239' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 35 sax

cement thru drill pipe. Mud to 220', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced

10 sax cement with Globe Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

Don Truman  
Conservation Division Agent