

15 -095-00249-00-00

KCC OIL/GAS REGULATORY OFFICES

Date: 6-17-16

District: 2

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 5123

API Well Number: 15-095-00249-00-00

Op Name: Pickrell Drilling Co

Spot: SESENE Sec 4 Twp 30 S Rng 8 E W

Address 1: 110 N. Market # 205

2970 Feet from N S Line of Section

Address 2: _____

330 Feet from E W Line of Section

City: Wichita

GPS: Lat: _____ Long: _____ Date: _____

State: KS Zip Code: 67202 -

Lease Name: Brown A Well #: 1

Operator Phone #: _____

County: Kingman

Reason for Investigation:

Status of well

Problem:

No record on file of well being plugged.

Persons Contacted:

Dave Pauley, Pickrell Drilling, Don Bramwell, BPI

Findings:

The location of the well was discovered because it had not been cleaned up and closed. The cellar of the well still present and we began digging with the Backhoe. We discovered a large amount of cement in the cellar and had to remove a cement slab 2 ft x 6ft x 6ft, in order to find the well. The Bowl of the 8 5/8 was still screwed onto the surface pipe and cement hard cement was found at the top of the Bowl. We asked the backhoe operator to pound on the cement inside the bowl with the teeth on the backhoe. We were unable to break the cement out of the bowl, so we decided the cement was good and the well was plugged. Attached info. shows well was plugged on 1-23-1986.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

Received
KANSAS CORPORATION COMMISSION
JUL 01 2016
CONSERVATION DIVISION
WICHITA, KS

Verification Sources:

- RBDMS
- T-1 Database
- Other: _____
- KGS
- District Files
- TA Program
- Courthouse

Photos Taken: Yes

By: Steve VanGieson

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

Form: _____

AUCTIONEERS

LEASE: Brown A
 FIELD: Spivey Grabs COUNTY: Kingman STATE: Kansas
 DESCRIPTION: SE/4 NE/4 and NE/4 SE/4 and S/2 SE/4 Sec. 4-30S-8W
 ACRES: 160 acres NET REVENUE INTEREST: 87.50% WORKING INTEREST: 100.00%

LEASE NUMBER: TAXES: \$450.54 (1996)
 CRUDE OIL PURCHASER: Koch Oil (Lse #11426) OPERATOR: Pickrell Drilling Company, Inc.
 GAS PURCHASER: Wichita Industrial Energy Corp.
 TRUCK OR PIPELINE: GRAVITY:
 Current Gas Price = \$2.145 per MCF (\$1.95 per MMBTU)

WELL NO:	PRODUCING FORMATION	DATE	B.O.P.D.	B.W.P.D.
1	P&A (1/86)			
2	Mississippi	9/97	10 MCFD 1/2 BOPD	2 BWPD

CUMULATIVE OIL PRODUCTION
 Gas 2,743,291 MCF
 Oil 34,565 Bbls
 (As of 11-30-97)

COMPLETION DATE: **GAS WELLS**
 1 May - 57 (P&A 1-23-86)
 2 11-26-69

Assignment Shows Entire Lease covering 162

INJECTION & SWD
 Docket # _____

EQUIPMENT:

SURFACE CASING:
 2 - 8 5/8" @ 204 w/ 155 sx.

PRODUCTION CASING:
 2 - 4 1/2" @ 4349 w/ 150 sx.

TUBING:
 2 - 4305 ft. 2 3/8" 4.7# E.U.E.

RODS:
 2 - 4241 ft. 3/4

PUMP:
 2 - 1 Ea. 2" x 1 1/4 x 12

PUMPING UNIT:
 2 - 1 Ea. American 114D Wide-base

ENGINE:
 2 - 1 Ea. C-66

TANK BATTERY:
 1 Ea. Tank, 12' x 10' 200 bbl. steel stock
 1 Ea. Tank, 7 1/2' x 10' steel S.W.

	Oil (Bbls.)	Gas (MCF)
1994	493	9574
1995	165	7521
1996	160	5086
1997		
Jan.		393
Feb.		409
Mar.		393
Apr.		403
May		376
Jun.		356
Jul.		350
Aug.		279
Sep.		302
Oct.		268
Nov.		214

Received
 KANSAS CORPORATION COMMISSION
JUL 01 2016
 CONSERVATION DIVISION
 WICHITA, KS

For 12 month period Oct. 1996 thru Sept. 1997 well sold 4,400 MCF.

Water is hauled.

