

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21492-00-00
Spot: NWSESWSW Sec/Twnshp/Rge: 34-22S-17W
368 feet from S Section Line, 962 feet from W Section Line
Lease Name: FRICK Well #: 1-34
County: PAWNEE Total Vertical Depth: 4300 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4064		WITH 2 SX CMT
PROD	4.5	4299	0	WITH 175 SX CMT
SURF	8.625	814		WITH 335 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/10/2016 10:00 AM

Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: CIBP @ 4064' WITH 2 SX CMT. PERFORATE AT 1100' & CIRCULATE IN & OUT OF 4 1/2" WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/10/2016 1:00 PM

KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

CIBP @ 4064' WITH 2 SX CMT. PERFORATE AT 1100'. PUMP 12 SX GEL WITH 525 SX CMT WITH 200# HULLS. CMT TO 0'

Top	Bot	Thru	Comments
4114	4120		
4113	4120		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING

Plugged through: CSG

District: 01

Signed

Ken Scofield
(TECHNICIAN) No

RECEIVED
AUG 17 2016
KCC DODGE CITY

AUG 31 2016

Form CP-2/3

KMS