

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20906-00-00
Spot: NESE Sec/Twnshp/Rge: 34-31S-33W
1959 feet from S Section Line, 662 feet from E Section Line
Lease Name: FAIR Well #: 1
County: SEWARD Total Vertical Depth: 5975 feet

Operator License No.: 9953
Op Name: HARRIS OIL & GAS COMPANY
Address: 1620 PENNSYLVANIA ST., #3A
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4875		WITH 2 SX CMT
CIBP		5530		WITH 2 SX CMT
PROD 5.5		5688	0	WITH 225 SX CMT
SURF 8.625		1504		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2016 8:30 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES Phone: (620) 629-3131

Proposed Plugging Method: CIBP @ 5530' WITH 2 SX CMT. CIBP @ 4875' WITH 2 SX CMT. PERFORATE AT 1555' WITH 50 SX CMT & 100# HULLS IN LAST 25 SX. PERFORATE AT 550' CIRCULATE TO SURFACE.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2016 11:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5530' WITH 2 SX CMT. CIBP @ 4875' WITH 2 SX CMT. PERFORATE AT 1555' WITH 50 SX CMT & 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 550' WITH 130 SX CMT. USED 5 SX CMT TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
5581	5589		
4927	4936		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed [Signature]

(TECHNICIAN) [Signature]

RECEIVED
AUG 17 2016
KCC DODGE CITY

AUG 31 2016

Form CP-2/3

KMS