

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-20233-00-00  
Spot: NWSESWNE Sec/Twship/Rge: 26-21S-34W  
3296 feet from S Section Line, 1977 feet from E Section Line  
Lease Name: HIPP HEIRS Well #: 1  
County: FINNEY Total Vertical Depth: 4910 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2715	0	WITH 200 SX CMT
SURF	8.625	398		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/18/2016 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L LOEB Phone: (719) 340-8985

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2016 2:15 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 300# HULLS & 80 SX CMT DOWN 4 1/2" CASING TO 2576'. DISPLACE WITH WATER TO 1750'. PRESSURE TO 500#. HOLDING. RUN CBL FROM 1500' TO 0'. NO CMT BEHIND 4 1/2" CASING. PERFORATE 4 HOLES AT 1100'. RUN TBG & PACKER TO 698'. INJECTION RATE 4 BPM AT 1200 PSI. PUMP 80 SX CMT & DISPLACE TO 990' AT 1100 PSI. TOOH WITH TBG & PACKER. PERFORATE 4 HOLES AT 450'. RAN TBG TO 700'. CIRCULATE CMT IN & OUT WITH 145 SX CMT. TOP OFF WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2555	2576		
2526	2528		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

no  
AUG 31 2016

RECEIVED  
AUG 22 2016  
KCC DODGE CITY



Form CP-2/3

KMS