

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-19009-00-01
Spot: NW Sec/Twnshp/Rgc: 27-32S-13W
3368 feet from S Section Line, 3852 feet from E Section Line
Lease Name: KELLY Well #: 2
County: BARBER Total Vertical Depth: 4494 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3810		WITH 2 SX CMT
PROD	4.5	4429	0	WITH 175 SX CMT
SURF	8.625	313		WITH 225 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/01/2016 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L LOEB Phone: (620) 886-2419

Proposed Plugging Method: CIBP @ 3810' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2016 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3810' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 4 1/2" AT 600'. RUN TBG IN HOLE TO 600'. PUMP DOWN TBG WITH 200 SX CMT. HAD FAIR TO NO RETURNS UP BACKSIDE OF TBG & BACKSIDE OF 4 1/2" CASING. WELL ON VACUUM. NEVER CIRCULATED ANY CMT TO SURFACE. SDON. 8/2/16: TAGGED TOC AT 1100' INSIDE 4 1/2" CASING. LOAD HOLE. UNABLE TO PUMP THROUGH PERFS AT 600'. PUMPED DOWN TBG FILLING 4 1/2" CASING WITH 50 SX CMT FROM 600' TO SURFACE. LAID TBG DOWN. PUMPED DOWN 4 1/2" X 8 5/8" ANNULUS WITH 50 SX CMT. MAXIMUM PRESSURE 475#. SHUT IN PRESSURE 200#.

Perfs:

Top	Bot	Thru	Comments
3860	3863		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED
AUG 18 2016
KCC DODGE CITY

AUG 31 2016

Form CP-2/3

KMS