

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40240-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 10-34S-12E
1589 feet from S Section Line, 2283 feet from E Section Line
Lease Name: COUNTY FARM A Well #: 15
County: CHAUTAUQUA Total Vertical Depth: 940 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD.	2.875	760		154 SX
SURF	10.75	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 06/28/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 900' gelled hole and spotted 3 sack plug. Pulled up to 700' and spotted 3 sack. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 10 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
918	932		
RECEIVED KCC DIST #3 AUG 18 2016 CHANUTE, KS DS			

Remarks:

Plugged through: TBG

District: 03

Signed

D. A. L.

(TECHNICIAN)

No

KCC WICHITA

AUG 22 2016

RECEIVED

AUG 31 2016

Form CP-2/3