

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25271-00-00
Spot: SWNWNESE Sec/Twushp/Rgc: 35-19S-25W
2278 feet from S Section Line, 991 feet from E Section Line
Lease Name: TANNER Well #: 1-35
County: NESS Total Vertical Depth: 4430 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4421	0	WITH 565 SX CMT
SURF	8.625	911		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/22/2016 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: PUMP 40 SX CMT & 150# HULLS THEN SPACER TO 1680' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2016 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN TBG TO 4410' & PUMPED 35 SX CMT & 150# HULLS. PULLED TBG TO 1670' & PUMPED 125 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 200#.

Perfs:

Top	Bot	Thru	Comments
4421	4430	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)

MM AUG 31 2016

RECEIVED
AUG 23 2016
KCC DODGE CITY MR

Form CP-2/3

12MS