

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20071-00-00
Spot: SWSWSENE Sec/Twnshp/Rge: 16-29S-39W
2712 feet from S Section Line, 1264 feet from E Section Line
Lease Name: ESSER HENRY Well #: 2
County: STANTON Total Vertical Depth: 2766 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2766	0	WITH 510 SX CMT
SURF	8.625	692		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/23/2016 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TBG IS STUCK IN HOLE. FIND FREE POINT AND CUT TBG. PULL UP ONE JOINT AND PUMP 100 SX CMT. LOAD HOLE & TEST CASING AT 600 PSI. RUN CBL FROM 1000'-0' TO VERIFY TOC. IF TOC IS BELOW 692' PERF SQUEEZE HOLE AND CIRCULATE CMT TO SURFACE WITH 255 SX CMT

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2016 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

8/22/16: CUT TBG AT 2005' & PULL UP TO 1975' & PUMP 100 SX CMT. 8/23/16" LOAD & TEST CASING TO 600 PSI. HOLDING. RAN CBL & FOUND TOC APPROXIMATELY 1000'. PERFORATE AT 840'. RTIH TO 830' & PUMP 15 BBLs WATER AT 600 PSI. NO BLOW OR RETURNS ON BACKSIDE. CIRCULATE 5 1/2" CASING WITH 110 SX CMT TO 0'. PUMP 50 SX CMT DOWN BACKSIDE TO 0'.

Perfs:

Top	Bot	Thru	Comments
2592	2725		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed _____

R. M. Sullivan
(TECHNICIAN)

RECEIVED
AUG 25 2016
KCC DODGE CITY

NO
AUG 31 2016

Form CP-2/3

KMS