

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-20255-00-00
Spot: NWNWSWSE Sec/Twnship/Rge: 9-28S-36W
1207 feet from S Section Line, 2545 feet from E Section Line
Lease Name: TATEMOORE Well #: 2
County: GRANT Total Vertical Depth: 2992 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2991	0	WITH 350 SX CMT
SURF	9.625	587		WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/19/2016 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TBG IS STUCK IN HOLE. BACK OFF TBG AS DEEP AS POSSIBLE(AT LEAST 1800'). PUMP 175 SX CMT. PULL OUT OF HOLE & WAIT ON CMT. TAG TOC. PERFORATE AT 500'. RTIH TO 700' & PUMP 240 SX CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2016 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

8/18/16: FOUND TBG WAS FREE. PULL UP TO 1800' & PUMP 175 SX CMT (PER KEN JEHLIK'S ORDERS). 8/19/16: TAGGED TOC @ 1464'. LOAD CASING & PRESSURE TO 300 PSI. HOLDING. PERFORATE AT 500'. RTIH TO 700' & PUMP 240 SX CMT. CIRCULATED CMT TO 0' OUT OF BACKSIDE. 8/22/16: CMT FELL INSIDE 7" TO 125'. TOPPED OFF WITH 45 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2821	2904		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed _____



(TECHNICIAN)

NO AUG 31 2016

RECEIVED
AUG 25 2016
KCC DODGE CITY



Form CP-2/3

