

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-27866-00-00  
Spot: SENEENE Sec/Twnshp/Rge: 4-35S-14E  
4809 feet from S Section Line, 69 feet from E Section Line  
Lease Name: STRICKLAND Well #: A6  
County: MONTGOMERY Total Vertical Depth: 1300 feet

Operator License No.: 30377  
Op Name: NELSON, DONALD & MARILYN  
Address: 1673 CR2100  
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1300		0 SX
SURF	8.625	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/31/2016 12:00 AM  
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: RON CUNNINGHAM Company: \_\_\_\_\_ Phone: (620) 330-2724

Proposed Pull rods and tubing out of hole, run 2" back in, gel hole, spot 5 sacks of cement on bottom, pull up to 500', spot 5 sacks of  
Plugging cement, pull up to 225', cement to surface, pull pipe out, top off cement, cut well head off below plow depth, restore  
Method: location.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/31/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Washed 2" to 1290' gelled hole and spotted 50' plug. Pulled up to 500' and spotted 50' plug.  
Pulled up to 225' and circulated cement to surface. Pulled 2" and topped well off. A total of 25  
sacks of cement were used to plug this well. Well was cut off and location restored.

RECEIVED  
KCC DIST # 3  
AUG 16 2016  
CHANUTE, KS


DS

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)

no AUG 31 2016

KCC WICHITA

AUG 22 2016

RECEIVED