

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-02887-00-00

Spot: NWNWSENE

Sec/Twnshp/Rge: 4-35S-14E

3828 feet from S Section Line,

1046 feet from E Section Line

Lease Name: HARRIS

Well #: OW-2

County: MONTGOMERY

Total Vertical Depth: 1300 feet

Operator License No.: 30377

Op Name: NELSON, DONALD & MARILYN

Address: 1673 CR2100

CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	1300		0 SX
------	-----	------	--	------

SURF	8.625	20		0 SX
------	-------	----	--	------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/01/2016 12:00 AM

Plug Co. License No.: 31696

Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP

Proposal Rcvd. from: RON CUNNINGHAM

Company:

Phone: (620) 330-2724

Proposed Pull rods and tubing out of hole, run 2" back in, gel hole, spot 5 sacks of cement on bottom, pull up to 500', spot 5 sacks of
Plugging cement, pull up to 225', cement to surface, pull pipe out, top off cement, cut well head off below plow depth, restore
Method: location.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/01/2016 2:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Washed 2" to 1330' gelled hole and spotted 50' plug. Pulled up to 500' and spotted 50' plug.
Pulled up to 225' and circulated cement to surface. Pulled 2" and topped well off. A total of 25
sacks of cement were used to plug this well. Well was cut off and location restored.

RECEIVED
KCC DIST # 3
AUG 16 2016
CHANUTE, KS


DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

NO AUG 31 2016

KCC WICHITA

AUG 22 2016

RECEIVED