

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20390-00-00
Spot: E2SESW Sec/Twnshp/Rge: 12-35S-31W
676 feet from S Section Line, 2810 feet from E Section Line
Lease Name: LARRY Well #: 2-12
County: SEWARD Total Vertical Depth: 3400 feet

| Operator License No.: <u>32126</u> | String | Size | Depth (ft) | Pulled (ft) | Comments |
|--|--------|-------|------------|-------------|-----------------|
| Op Name: <u>ROBERTS, GERALD M. DBA SUNFIRE E</u> | CIBP | | 2995 | | WITH 2 SX CMT |
| Address: <u>701 S PARKWAY BLVD PO BOX 1761</u> | PROD | 5.5 | 3388 | 0 | WITH 200 SX CMT |
| <u>LIBERAL, KS 67901</u> | SURF | 8.625 | 1536 | | WITH 750 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/04/2016 12:30 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Revd. from: STEVE MCADAMS Company: LONESTAR SERVICES Phone: (620) 629-3131

Proposed Plugging Method: CIBP @ 2995' WITH 2 SX CMT. CUT CASING AT 1630'. PLUG AT 1580' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2016 2:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

8/4/16: SET CIBP @ 2995' WITH 2 SX CMT. CUT AT 1630' WASN'T FREE. PERFORATE AT 1580'. PUMPED IN TO IT. PRESSURED UP TO 600 PSI. PUMPED TO 1000 PSI. PUMPED 33 BBLs AT 1000 PSI. NO CIRCULATION. RTIH TO 1600'. 8/5/16: SPOT 65 SX CMT. PULL TBG OUT OF HOLE. DISPLACED 2 BBL WATER DOWN AT 1000 PSI. WOC. TAGGED CMT AT 1100'. PERFORATE AT 550'. PUMPED IN TO IT. PRESSURED TO 500 PSI. NO BLOW ON BACK SIDE. RTIH TO 550' & SPOT 50 SX CMT. PULL TBG OUT. PERFORATE AT 45'. CIRCULATED TO 0' WITH 30 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3067 | 3069 | | |
| 3039 | 3045 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

District: 01

Signed B. W.

(TECHNICIAN)

RECEIVED
AUG 17 2016
KCC DODGE CITY

AUG 31 2016

Form CP-2/3

KMS