

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-077-21859-01-00
 Spot: N2N2NWNE Sec/Twnshp/Rge: 7-35S-7W
300 feet from N Section Line, 1980 feet from E Section Line
 Lease Name: VORNAUF Well #: 2-18H
 County: HARPER Total Vertical Depth: 4882 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|--------|------------|-------------|---------------|
| COND | 20 | 100 | | 11 sx cement |
| | 11 7 | 5404 | | 290 sx cement |
| | L1 4.5 | 9999 | | |
| PROD | 7 | 5454 | | 290 SX |
| SURF | 9.63 | 832 | | 420 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2016 12:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: RON ORR Company: ORR ENTERPRISES Phone: (580) 430-4517

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 08/01/2016 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4850', RELEASED PLUG & CIRCULATED 180 BBLs OF MUD & FOLLOWED WITH 20 SKS OF CEMENT. RECOVERED 27 JOINTS 1184' OF 7" CASING. TRIPED IN HOLE WITH TUBING TO 1350' & SPOTTED 60 SKS CEMENT. PULL TUBING TO 900' & SPOTTED 50 SKS CEMENT. PULLED TUBING TO 300' & CIRCULATED WITH 100 SX CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 8800 | 8803 | | |
| 8482 | 8485 | | |
| 8163 | 8166 | | |
| 7849 | 7852 | | |
| 7530 | 7534 | | |
| 7213 | 7217 | | |
| 6895 | 6898 | | |
| 6577 | 6581 | | |
| 6260 | 6263 | | |
| 5942 | 5946 | | |
| 5626 | 9999 | | |

Remarks: CLASS C CEMENT. ORR ENT. TMD = 11,693

Plugged through: TBG

District: 02

Received
 KANSAS CORPORATION COMMISSION Signed

[Signature]
 (TECHNICIAN)

AUG 25 2016

[Signature]
AUG 31 2016

CONSERVATION DIVISION
 WICHITA, KS