

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21373-00-00  
Spot: SENESESE Sec/Twnshp/Rge: 31-32S-19W  
845 feet from S Section Line, 169 feet from E Section Line  
Lease Name: BIRD A Well #: 1-31  
County: COMANCHE Total Vertical Depth: 6065 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 5081       |             | WITH 10 SX CMT  |
| COND   | 20    | 77         |             | WITH 8 SX CMT   |
| PROD   | 4.5   | 5320       | 1506        | WITH 135 SX CMT |
| SURF   | 8.625 | 650        |             | WITH 325 SX CMT |

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2016 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5081' WITH 10 SX CMT. PLUG AT 940' WITH 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2016 11:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5081' WITH 10 SX CMT. 1ST PLUG AT 940' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 5163 |      |      |          |
| 5161 |      |      |          |
| 5160 |      |      |          |
| 5158 |      |      |          |
| 5146 |      |      |          |
| 5144 |      |      |          |
| 5142 |      |      |          |
| 5140 |      |      |          |
| 5138 |      |      |          |
| 5131 | 5163 |      |          |

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
AUG 18 2016  
KCC DODGE CITY *AD*

Signed [Signature]  
(TECHNICIAN) *no*

AUG 31 2016

*kms*