

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-11150-00-00  
Spot: W2NENWNE Sec/Twnshp/Rge: 34-34S-2E  
4935 feet from S Section Line, 1900 feet from E Section Line  
Lease Name: POST Well #: 2  
County: SUMNER Total Vertical Depth: 3498 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3448	250	40 SX
SURF	8.625	127		7 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2016 10:00 AM  
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.  
Proposal Rcvd. from: ROSCOE MENDENHALL Company: STELBR OIL Phone: (316) 264-8378

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/08/2016 5:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 3400' W/2 SX CUP. SET ANOTHER CIBP @ 260' SHOT OFF PROD. CASING AT 250' AND PULLED. RAN BACK IN WITH 2 7/8" TUBING TO 250' AND PUMPED CEMENT OPERATOR CIRCUALTED 125 SX TO SURFACE. TOPPED OFF WITH AN ADDITIONAL 20 SX. 60/40 POZ-MIX W/4% GEL AND 1/4 # PER SACK OF POLY FLAKE. CAME BACK AND CUT OFF CASING BELOW SURFACE ABOUT 4 FOOT. CONSOLIDATED OILWELL SERVICE OUT OF EL DORADO KS. TICKET #51281. JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3448	3484	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

Received  
KANSAS CORPORATION COMMISSION

AUG 25 2016

CONSERVATION DIVISION  
WICHITA, KS

Daniel B. Fox  
(TECHNICIAN)

no  
AUG 31 2016

Form CP-2/3

✓/X