

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21635-00-00
Spot: SESENE Sec/Twnshp/Rge: 36-25S-17W
2954 feet from S Section Line, 293 feet from E Section Line
Lease Name: CROCKETT Well #: 36-1
County: EDWARDS Total Vertical Depth: 4876 feet

Operator License No.: 34886
Op Name: TOTO ENERGY, LLC
Address: 25815 OAK RIDGE DR
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4425		WITH 2 SX CMT
COND	13.375	56		WITH 90 SX CMT
PROD	5.5	4876	1768	WITH 250 SX CMT
SURF	8.625	265		WITH 250 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/02/2016 1:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: TERRY MADDEN Company: TOTO ENERGY Phone: (713) 623-2183

Proposed Plugging Method: CIBP @ 4425' WITH 2 SX CMT. PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. PLUG AT 315' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2016 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

CIBP @ 4425' WITH 2 SX CMT. 1ST PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT WAS FALLING AT SURFACE. PUMPED 25 SX CMT TO FILL HOLE. 8/4/16: CMT FELL 160'. TOPPED OFF WITH CMT.


Top	Bot	Thru	Comments
4392	4414		

Remarks: USED 60/40 POZMIX 4% GEL BY GRESSEL OILFIELD SERVICE.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG - 5 2016
KCC DODGE CITY

AUG 31 2016

Form CP-2/3