

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-21641-00-00  
Spot: W2W2E2SE Sec/Twnshp/Rge: 16-25S-16W  
1318 feet from S Section Line, 1086 feet from E Section Line  
Lease Name: ACOUSTIC GUITAR Well #: 16-1  
County: EDWARDS Total Vertical Depth: 4820 feet

Operator License No.: 34886  
Op Name: TOTO ENERGY, LLC  
Address: 25815 OAK RIDGE DR  
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4410		WITH 2 SX CMT
COND	13.375	55		WITH 100 SX CMT
PROD	5.5	4807	1700	WITH 275 SX CMT
SURF	8.625	359		WITH 340 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/29/2016 12:00 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: TERRY MADDEN Company: TOTO ENERGY Phone: (620) 804-2202

Proposed Plugging Method: CIBP @ 4410' WITH 2 SX CMT. PLUG AT 1150' WITH 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/29/2016 5:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

CIBP @ 4410' WITH 2 SX CMT. 1ST PLUG AT 1154' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT FELL. PUMPED ANOTHER 100 SX CMT. 8/1/16: CMT FELL 35' FROM SURFACE. TOPPED OFF HOLE WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4464	4472		

Remarks: USED 60/40 POZMIX 4% GEL BY GRESSEL OILFIELD SERVICES.

Plugged through: CSG

District: 01

Signed

*Ken Scofield*

(TECHNICIAN)

SA

no

RECEIVED  
AUG - 5 2016  
KCC DODGE CITY

AUG 3 1 2016

Form CP-2/3