

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-01728-00-01
Spot: NESW Sec/Twnshp/Rge: 8-33S-12W
1918 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BOGGS Well #: VI-8 OWWO
County: BARBER Total Vertical Depth: 4927 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5822</u>	CIBP		4525		WITH 2 SX CMT
Op Name: <u>VAL ENERGY, INC.</u>	PROD	5.5	4846	2810	WITH 125 SX CMT
Address: <u>125 N MARKET ST STE 1110</u> <u>WICHITA, KS 67202</u>	SURF	8.625	250		WITH 190 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/27/2016 10:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: SAND BACK & 4 SX CMT OR SET CIBP @ 4525' & 2 SX CMT. PLUG AT 625' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2016 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4525' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 276' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4624	4640		
4583	4605		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG - 3 2016
KCC DODGE CITY

700
AUG 31 2016

Form CP-2/3