

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22778-00-01
Spot: SWSE Sec/Twnshp/Rge: 18-34S-11W
645 feet from S Section Line, 2001 feet from E Section Line
Lease Name: MICHEL Well #: 1
County: BARBER Total Vertical Depth: 5350 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4504		WITH 2 SX CMT
CIBP		4610		
PROD	4.5	5331	2800	WITH 230 SX CMT
SURF	13.375	237		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/04/2016 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4500' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 70 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2016 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4504' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 283' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4632	4640		
4564	4570		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed

S. Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG 18 2016
KCC DODGE CITY

AUG 31 2016

Form CP-2/3

KMS