

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24369-00-00
Spot: SESWNWNW Sec/Twnshp/Rge: 17-32S-8E
4241 feet from S Section Line, 4945 feet from E Section Line
Lease Name: BUTTS Well #: 17-2
County: COWLEY Total Vertical Depth: 1892 feet

Operator License No.: 34798
Op Name: VIKING PRODUCTION LLC
Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1892		75 SX
PROD	4.5	1943		75 SX
SURF	8.625	464		75 SX
T1	2.375	1851		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/18/2016 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: BERT CARLSON Company: _____ Phone: (620) 485-6064

Proposed Plugging Method: Set bottom plug 50 ft above perforations. Pull casing and set top plug 50 ft surface requirements.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/04/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 1800', SYNDER CEMENTING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1682'. RIH ON WIRELINE CUT CASING @ 913', 821', & 694' LAYED DOWN 23 JOINTS 4-1/2" CASING (694'). RIH W/TBG @ 515', SNYDER CEMENTING MIXED & PUMPED 120 SXS CLASS A COMMON. CEMENT DID NOT CIRCULATE. 08/04/2016, TAGGED CEMENT PLUG @ 110', RIH W/TBG @ 95', SNYDER CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS CLASS A COMMON TO SURFACE, CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
1867	1871		
1861	1865		
1846	1852		
1825	1835		

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

JK
AUG 31 2016

Form CP-2/3