

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24350-00-00  
Spot: SENE Sec/Twnshp/Rge: 18-32S-8E  
990 feet from N Section Line, 330 feet from E Section Line  
Lease Name: BUTTS Well #: 18-1  
County: COWLEY Total Vertical Depth: 1950 feet

Operator License No.: 34798  
Op Name: VIKING PRODUCTION LLC  
Address: 1432 NIGHTHAWK RD.  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1945		75 SX
PROD	4.5	1994		75 SX
SURF	8.625	465		150 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2016 8:00 AM  
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.  
Proposal Rcvd. from: BERT CARLSON Company: \_\_\_\_\_ Phone: (620) 485-6064

Proposed  
Plugging  
Method:

Set bottom plug 50 ft above perforations. Pull casing and set top plug 50 ft below surface requirements.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/29/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 1770', SNYDER CEMENTING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1597'. RIH ON WIRELINE CUT CASING @ 803', LAYED DOWN 19 JOINTS 4-1/2" CASING. RIH W/TBG @ 508', SNYDER CEMENTING MIXED & PUMPED 120 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
1856	1885	CSG	

Remarks: COMPLAINCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

JK  
AUG 31 2016

Form CP-2/3