

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24345-00-00  
Spot: SWNWNWNW Sec/Twnshp/Rge: 17-32S-8E  
4885 feet from S Section Line, 5019 feet from E Section Line  
Lease Name: BUTTS Well #: 17-1  
County: COWLEY Total Vertical Depth: 1833 feet

Operator License No.: 34798  
Op Name: VIKING PRODUCTION LLC  
Address: 1432 NIGHTHAWK RD  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1833		40 SX
PROD	4.625	1836		40 SX CMT
SURF	7	450		105 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2016 8:00 AM  
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.  
Proposal Rcvd. from: BERT CARLSON Company: \_\_\_\_\_ Phone: (620) 485-6064

Proposed Plugging Method: Set bottom Plug 50 ft. above perforations. Pull casing and set top plug 50 ft below surface requirements

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/29/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TGB @ 1770', SNYDER CEMENTING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1515'. RIH ON WIRELINE CUT CASING @ 803', LAYED DOWN 19 JOINTS 4-1/2" CASING. RIH W/TBG @ 508', SNYDER CEMENTING MIXED & PUMPED 120 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
1756	1772	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

*DK*

AUG 31 2016

Form CP-2/3

*1/2*