

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24351-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 18-32S-8E
3244 feet from S Section Line, 1225 feet from E Section Line
Lease Name: BUTTS Well #: 18-2
County: COWLEY Total Vertical Depth: 1924 feet

Operator License No.: 34798
Op Name: VIKING PRODUCTION LLC
Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1918		60 SX
SURF	8.625	451		165 SX
T1	2.375	1850		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/18/2016 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: BERT CARLSON Company: _____ Phone: (620) 485-6064

Proposed Plugging Method: Set bottom plug 50 ft above perforations.. PUII casing and set top plug 50 ft below surface casing requirements.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/26/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TBG @ 1830', SNYDER CEMENTING MIXED & PUMPED 20 SXS CLASS A COMMONG & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1684'. RIH ON WIRELINE CUT CASING @ 890' & 751, LAYED DOWN 16 JOINTS 4-1/2" CASING (751'). RIH W/TBG @ 508', SNYDER CEMENTING MIXED & PUMPED 120 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED.

Top	Bot	Thru	Comments
1856	1870		

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

NO Form CP-2/3
AUG 31 2016

JK