

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24368-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 8-32S-8E  
283 feet from S Section Line, 4615 feet from E Section Line  
Lease Name: BUTTS Well #: 1-AUG  
County: COWLEY Total Vertical Depth: 1940 feet

Operator License No.: 34798  
Op Name: VIKING PRODUCTION LLC  
Address: 1432 NIGHTHAWK RD  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		1790		
PROD	4.5	1939		110 SX
PROD	4.5	1940		117 SX
SURF	8.625	467		117 SX
T1	2.375	1892		

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.  
Proposal Rcvd. from: BERT CARLSON Company: \_\_\_\_\_ Phone: (620) 485-6064

Proposed Plugging Method: Set bottom plug 50 ft above perforations. Pull casing and set plug 50 ft below surface casing requirements.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/05/2016 5:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

**Perfs:**

RIH W/ TBG @ 1910', SNYDER CEMENTING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1835'. RIH ON WIRELINE CUT CASING @ 550', LAYED DOWN 11 JOINTS 4-1/2" CASING. 07/01/2016, RIH W/TBG @ 525', SNYDER CEMENTING MIXED & PUMPED 100 SXS CLASS A COMMON, CEMENT DID NOT CIRCULATE. 07/05/2016 TAGGED CEMENT PLUG @ 100' RIH W/ TBG @ 95', SNYDER MIXED & PUMPED 40 SXS CLASS A COMMON TO SURFACE. TAGGED CEMENT PLUG @ 31', SNYDER TOPPED WELL BACK TO SURFACE W/10 SXS

Top	Bot	Thru	Comments
1926	1930		
1920	1924		
1902	1930		

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

*DUANE KRUEGER*  
(TECHNICIAN)

*no*  
AUG 31 2016