

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 009 21 341 ⁰⁰⁰⁰⁰ (of this well)

Operator's Full Name Messman-Rinehart Corp.

Complete Address 1432 KSB&T Bldg., Wichita, Kansas, 67202

Lease Name Zajic Well No. 1

Location C N/2 SE SE Sec. 13 Twp. 16 Rge. 11 XXX (W) X

County Barton Total Depth 3426'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:30 PM Day 25 Month 9 Year 1979

The above well was plugged as follows:

Sanded back to 3375' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

25 sx mud gel, plug, and 100 sx cement.

Max pres. 900#. Shut in pres. 400#.

Recovered 2400' of 4 1/2" casing.

3421' of 4 1/2" casing cemented with 50 sx cement.

333' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-26-79

INV. NO. 0548-W

Signed: Duan Rankin
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
09-26-79 SEP 26 1979
CONSERVATION DIVISION
Wichita, Kansas