


15-009-064810000



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION ~~SE~~ NEC SW

SEC. 15 TWP. 16 RGE. 11 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Laudick

Operator Bradley Oil Co Address Wichita - Kansas. Box 1400

Field _____ County Barton

Total Depth 3360 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 298 ft. Circulated with cement
5/8 casing at 3352 ft. - Plugged back down bottom
to 3215 ft with true Wells' Plug & Chat. - Mixed
15 sacks of cement at 3215 ft. - Shot off & pulled the 5/8
casing - Filled with mud to 250 ft. - Back bridge & 15 sacks
of cement at 250 ft. - Mud to 30 ft. - Plug & 10 sacks of
cement at the surface.

RECEIVED

3-29-49
MAR 29 1949

PLUGGING
FILE SEC 15 T 16 R 11 W
BOOK 88 PAGE 36

C. W. Starnock
District Conservation Agent
KANSAS

Date 3-25-49

