

RECEIVED  
OCT 7 1982  
STATE CORPORATION COMMISSION  
Wichita, Kansas  
CONSERVATION DIVISION

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-009-20743-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Southern States Oil Co.

Complete Address P.O. Box 1365, Great Bend, Mo. 67530

Lease Name Esfeld Well No. 1

Location SE NW SE Sec. 15 Twp. 16 Rge. 11 (East) (West)

County Barton Total Depth 3359'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Mo. 67524 License No. 6050

Operation Completed: Hour: 11:15 AM Day: 29 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 194' SP. cased w/ 150 sacks cement. 5 1/2" set at 3358' w/ 125 sacks cement  
Top perf. 3197'. Plugged bottom plug w/ sand & 5 sacks cement to 3100'. Shot pipe  
3 times & recovered 2385'. Ordered 140 sacks 50 permix - 4% Gel - 376 lb. G., 5 sacks  
hulls, 15 sacks Gel & 8 5/8" plug. Pumped in 8 5/8" SP, 4 sacks hulls, 12 sacks Gel,  
70 sacks cement, 3 sacks Gel, 1 sack hulls, released plug & followed w/ 70 sacks cement

Maximum pressure 800 pounds

Amount of Surface Casing: 194' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICE

DATE 10-14-82  
INV. NO. 1353-W